SPECIFICATIONS
310-1107370

ITEM NO.	DESCRIPTION	CHECK IF AS SPECIFIED	DESCRIBE FULLY IF NOT AS SPECIFIED
1.	Chemically clean and flush AHU heating coils and Hydronic piping on the Air Handler Hot Deck Coils for two buildings, WC ADAM and WC BAKER, Both boilers are Weil McClain Water Tube boilers, and they were manufactured in 1996. M/N – WM778-W-GP, 3 inch piping		
	Contractor will be responsible for Propylene Glycol removal, disposal and refilling system		
	Contractor to provide all necessary supplies and equipment.		
	All Work to be completed by a current Washington State Licensed insured contractor / technician for boiler repair. Contractor to provide a copy of Liability of insurance before work is started		
	When work is complete leave job site neat and clean		
	Warranty: At least 90 days from the completion of the repairs.		