SPECIFICATIONS FR1065427

Page 1 of 2 Eleanor Chase House WR Carpet Flooring

ITEM		CHECK IF	DESCRIBE FULLY IF
NO.	DESCRIPTION	AS	NOT AS SPECIFIED
		SPECIFIED	
1	Existing Flooring to be removed and floor / substrate prepared as per		
	manufacturer's directions. Dispose of existing old floor covering		
	Furnish and install new Carpet tile.		
	Same Vinyl product used throughout the Main Floor Haul way		
	Carpet Tile CEO Modular Bigelow Commercial 24" x 24" or equal / better		
	Tufted, multi-colored loop, Colorstrand Nylon		
	Color is CEO Modular or similar, final selection of color at time of order.		
	Hall Size: see attached building Plan:		
	Total square yards needed: 174 yard plus stair case area		
	See drawing.		
	Installation will be performed by an authorized / trained technician.		
	Gauge: 1/10 (39.37 Rows per 10 cm		
	Pile Weight: 16.0 oz per sq yd		
	Pile Thickness: .096 inch		
	Stitches per inch: 10.7		
	Density: 6000 Weight Density: 96,000		
	Construction: Tuffed		
	Backing Foundation: Ultraset – Fiberglass Reinforced Thermopla Composite Tile.		
	Size: 24" x 24" square		
	Flamous IIII A OTAM F 0.40 OL A OO A (OLLIF DOWN)		
	Flammability: ASTM E 648 CLASS 1 (GLUE DOWN)		
	Green Label: 1098		
	CRI Rating: for Severe Traffic		
	Warranty: Lifetime Ultra set Modular Warranty, Limited colorfastness to light, 10-		
	Year Commercial Warranty		

SPECIFICATIONS FR1065427

Page 2 of 2 Eleanor Chase House WR Carpet Flooring

Tool Inventory	
All vendors on site will have to have a quick briefing on Security issues. Vendors must	
submit an inventory of all tools that will be on the job site.	
Mandatory Pre-Bid Visit	
All Bidders Must ATTEND	
Location: Dept. of Corrections, 427 W. 7 th Ave., Spokane, WA 99204	
Contact Name: Grace Engelhard @ (509) 363-8107 or Laura Jense @ (509)	
227-7012	
Date: Thursday, May 6 th at 10:00 am PST	
Plus 10% of the selected tile to be left on site for future repairs	
Dept. of Corrections is not aware of any asbestos materials that could	
be disturbed by the project. However the Dept. of Corrections has an	
asbestos survey on site and can be made available to contractors	
during the pre-bid walk through.	
All Proposals shall meet or exceed the requirements of all applicable	
local governing codes. Comply with all regulations pertaining to	
prevailing wages.	