



NOTICE TO CONTRACTORS
HIGHWAY CONSTRUCTION

March 22, 2010

Sealed bids will be received in the Bid Room SA-19, located on the service level of the Department of Transportation, 310 Maple Park Avenue SE, Olympia, Washington, 98501 until 11:00:59 am Pacific Time, or at P.O. Box 47360, Olympia, Washington, 98504-7360, until 11:00:59 am Pacific Time or electronically via BidX.com until 11:00:59 am Pacific Time, on the dates shown below.

All bid proposals shall be accompanied by a bid proposal deposit in cash, certified check, cashier's check or surety bond in an amount equal to five percent (5%) of the amount of such bid proposal. Should the successful bidder fail to enter into a contract and furnish a satisfactory performance bond, the bid proposal deposit shall be forfeited.

Bonds submitted on other than the bond form provided by the department may be subject to rejection.

It is the Washington State Department of Transportation's (WSDOT) policy to assure that no person shall, on the grounds of race, color, national origin and sex, as provided by Title VI of the Civil Rights Act of 1964, be excluded from participation in, be denied the benefits of, or be otherwise discriminated against under any of its federally funded programs and activities. Any person, who believes his /her Title VI protection has been violated, may file a complaint with WSDOT's Office of Equal Opportunity (OEO). For Title VI complaint forms and advice, please contact OEO's Title VI Coordinator at (360) 705-7098.

WSDOT hereby gives public notice that it is the policy of the department to assure full compliance with Title VI of the Civil Rights Act of 1964, the Civil Rights Restoration Act of 1987, and related statutes and regulations in all programs and activities. Persons wishing information may call the Washington State Department of Transportation, Office of Equal Opportunity at (360) 705-7098.

The right is reserved to reject any and all bids and to waive informalities in the bidding.

Bidding proposal may not be issued to bidders unless they are prequalified, except where otherwise provided in Plans and Specification. For those contractors who are not prequalified, application for prequalification will be submitted on DOT Form 420-010 (Standard Questionnaire and Financial Statement) and must be received by the Prequalification Engineer no less than fifteen days prior to the scheduled bid opening to receive consideration for issuance of a bidding proposal for that bid opening.

Informational copies of plans and specifications are on file in the office of the County Engineer of the County in which the work is situated, the chapter offices of the Associated General Contractors of America in Seattle, Spokane, and Tacoma, and the offices of the Regional Administrators or the Headquarters of the Department of Transportation, where they may be inspected. The use of informational proposals shall be allowed only upon written request and will be accepted only when written authority for their use has been granted.

FEE

Project Documents will be furnished for the non-refundable fee of: **\$ 25.00 Plus Sales Tax**

(Remittance may be made to the Washington State Treasurer and sent to the address below).

TO ORDER PLANS AND SPECIFICATIONS PLEASE CALL (360) 705-7835 (from 8:00 am to 5:00 pm) or (360) 705-7014 (24-Hour Recording). To order by mail, the address is: Contract Ad & Award Administration Office, Washington State Department of Transportation, P.O. Box 47360, Olympia, WA 98504-7360. Current Bid Results are available through the Internet address below.

Electronic Project Plans, Specifications, Geotechnical Reports, Addenda, Planholders Lists, Award/Bid Status, and Bid Tabulations are available on the Internet at:

<http://www.wsdot.wa.gov/biz/contaa>

ESTIMATE RANGES PUBLISHED IN THIS NOTICE MUST NOT BE USED AS A BASIS FOR BID PREPARATION.

Americans with Disabilities Act (ADA) Information

If you would like copies of this document in an alternative format - large print, Braille, cassette tape, or on computer disk, please call Washington State Telecommunications Relay Service TT 1-800-833-6388, Tele-Braille 1-800-833-6385, Voice 1-800-833-6384, and ask to be connected to (360) 705-7097.

Individuals requiring reasonable accommodation may request written materials in alternate formats, sign language interpreters, physical accessibility accommodations, or other reasonable accommodation by contacting the event sponsor Dave Mariman 360-705-7017, usually 2 weeks before the bid opening. Persons with hearing impairments may call Washington State Telecommunications Relay Service TT 1-800-833-6388 Tele-Braille 1-800-833-6385, Voice 1-800-833-6384, and ask to be connected to the event sponsor's phone number.

BID OPENING WEDNESDAY, MARCH 31, 2010

- *1. (LEWIS & THURSTON) **BLAKESLEE JUNCTION RR XING TO GRAND MOUND I/C – ADD**
*** **LANE** (CL 1 or 4, \$20,000,000 - \$30,000,000) **CONTAINS VOLUNTARY MWBE GOAL: 19%.** A State Project on I-5, MP 83.66 to MP 87.56. **CONTAINS APPRENTICE UTILIZATION REQ: 15%.** Requires: Grading, constructing drainage, surfacing, paving with hot mix asphalt, constructing reinforced concrete retaining wall, soldier pile walls, seismic retrofit to bridge, precast reinforced concrete three-sided structure, intelligent transportation system, illumination system, permanent signing, guardrail, concrete barrier, pavement markings, rumble strips, stormwater ponds, roadside planting, erosion control, traffic control and other work. 275 Working days. Involves 174 items. 198910 CY rdwy excav incl haul, 66010 CY pond excav incl haul, 86430 T special borrow incl haul, 52450 CY embank comp, 12713 T quarry spalls, 14064 LF horizontal drains, 14074 LF media filter drain, 52 EA catch basin, 6389 LF sch A storm sewer pipe, 1980 LF shaft, 2078 LF furnish soldier pile, 112500 LB st rebar, 1765 CY conc CL 4000, 3819 SF lagging, 750 LF traffic barrier, 285 LF soldier pile wall traffic barrier, 5293 SF conc fascia panel, 176470 T crushed surface base course, 77570 T HMA CL 1/2 IN PG 64-22, 23930 SY perm erosion control blanket, 149150 SY compost blanket, 8230 LF silt fence, 23120 LF high visibility silt fence, 3570 LF wattle, 30 ACRE seed, fert, mulch, seed mix, 17500 CY topsoil, 82000 EA shrub mix, 9770 CY bark or wood chip mulch, 16120 LF high visibility fence, 3888 LF extruded curb, 7463 LF beam guardrail, 18154 LF single-slope conc barrier, 38199 LF temp conc barrier, 1050 LF differential grade median barrier, 86860 LF paint line, 74320 LF profiled plastic line, 295850 LF temp pvmt marking, 551 SF const signs CL A, 4287 CY struct excav CL B incl haul, 30263 SF shoring or extra excav CL B, 44730 LF wire fence, 5200 LF temp fence, 8470 SY const geotextile. **CONTAINS MINIMUM BID ITEM: TYPE B PROGRESS SCH.** Lump Sum Bids for: Temp access rd, shoring or extra excav CL A, seismic retrofit, column jacketing, precast reinf conc three-sided struct, perm signing, cantilever sign struct, illum sys, comm conduit sys, comm cables and interfaces, data station sys, CCTV sys, video/data dist and trans sys, VMS, wireless comm sys, temp traffic control, cure box, survey, clean exist drain struct, transport field office bldg, SPCC plan.(XL-3224)(400508W)(09X318)(7903)(6 of 6)(1)
- *2. **“THIS PROJECT IS FUNDED IN WHOLE OR IN PART BY FUNDS MADE AVAILABLE**
*** **THROUGH THE AMERICAN RECOVERY AND REINVESTMENT ACT”** (MASON, THURSTON, KITSAP) **OLYMPIC REGION CABLE BARRIER** (CL 11, \$1,000,000 - \$1,250,000) **CONTAINS CONDITION OF AWARD DBE GOAL: 4%.** F.A. No. ARRA-9999(576) on US 101, MP 350.12 to MP 362.09 and SR 303, MP 7.25 to MP 7.63. Requires: Installing high tension cable barrier in median areas, slope flattening, seeding and fertilizing by hand, traffic control and other work. 55 Working days. Involves 17 items. 1085 LF silt fence, 41400 LF high-tension cable barrier sys. Lump Sum Bids for: Additional high-tension cable barrier components, perm signing, temp traffic control, SPCC plan.(XL-3730)(310101T)(10C501)(7914)(4 of 4)(1)
- *3. (KITSAP & MASON) **OLD SR 3 TO 0.4 MILES S. OF ANDERSON HILL RD.** (CL 4, \$2,000,000 –
*** \$2,500,000) **CONTAINS VOLUNTARY MWBE GOAL: 6%.** A State Project on SR 3, MP 22.00 to 44.30. **CONTAINS APPRENTICE UTILIZATION REQ: 15%.** Requires: Pavement repairs, overlaying, planing and paving with hot mix asphalt, roadway delineation, adjusting catch basins and monument cases, minor electrical work, traffic control and other work. 33 working days. Involves 52 items. 5 MI shoulder finish, 17920 T HMA CL 1/2 IN PG 64-22, 104400 LF paint line, 66850 LF profiled plastic line, 80760 LF temp pvmt marking, 548 SF const signs CL A. Lump Sum Bids for: Transverse rdwy rumble strip, temp traffic control, SPCC plan.(XL-3496)(300382A)(09C532)(7912)(4 of 4)(1)

- *4. **(WHATCOM) GALLUP CREEK BRIDGE REPLACEMENT** (CL 1 or 6, \$3,000,000 - \$4,000,000)
 *** **CONTAINS VOLUNTARY MWBE GOAL: 9%.** A State Project on SR 542, MP 33.31 to MP 33.49.
CONTAINS APPRENTICE UTILIZATION REQ: 15%. Requires: Constructing a bridge, two structural earth walls, grading, HMA paving, channelization, drainage, pavement marking, permanent signing, guardrail, temporary and permanent illumination systems, erosion control, planting, traffic control and other work. 237 Working Days. Involves 147 items. 2886 CY rdwy excav incl haul, 12350 T select borrow incl haul, 6720 CY embank comp, 1103 CY channel excav incl haul, 9 EA catch basin, 295 LF CL V reinf conc storm sewer pipe, 114 LF ductile iron pipe, 650 LF PVC pipe, 205 LF st casing, 481 CY soil excav incl haul, 67 LF furnish & place temp casing, 13 LF furnish perm casing, 135660 LB st rebar, 193 CY conc CL 4000, 568 LF prestressed conc girder, 328 LF bridge rail, 330 LF traffic barrier, 3480 SF struct earth wall, 233 SY bridge approach slab, 1700 T permeable ballast, 2210 T crushed surface base course, 1650 T HMA CL 1/2 IN PG 58-22, 2050 SY organic erosion control blanket, 8601 SY wet native seed & mulch, 124 EA grand fir, 1428 EA salmonberry, 1590 EA western sword fern, 969 EA Indian plum, 456 EA snowberry, 800 SY live brush mattress, 12248 SY soil amend, 4619 SY bark or wood chip mulch, 444 LF weathering st beam guardrail, 898 LF temp conc barrier, 5240 LF paint line, 1433 CY struct excav CL B incl haul, 652 SY const geotextile. **CONTAINS MINIMUM BID ITEM: TYPE B PROGRESS SCH.** Lump Sum Bids for: Temp bridge, shoring or extra excav CL A, stream diversion, perm signing, temp illum sys, illum sys, temp traffic control, cure box, struct survey, rdwy survey, abandon piezometer, temp dewatering sys, SPCC plan. **SUPERSTRUCTURE INCLUDES:** 35400 LB epoxy-coated st rebar, 3400 LB st rebar, 126 CY conc CL 4000D, 22 CY conc CL 4000, 42 LF strip seal expansion jnt sys, 10 EA elastomeric bearing pad, 20 EA elastomeric transverse stop pad. (XL-2829)(154229G)(09A024)(7911)(4 of 4)(1)
- *5. **“THIS PROJECT IS FUNDED IN WHOLE OR IN PART BY FUNDS MADE AVAILABLE THROUGH THE AMERICAN RECOVERY AND REINVESTMENT ACT”**
 ** **(CLARK) I-5 TO 164TH INTERCHANGE PAVING** (CL 4, \$3,000,000 - \$4,000,000) **CONTAINS**
 *** **CONDITION OF AWARD DBE GOAL: 9%.** F.A. No. ARRA-STPF-0014(068) on SR 14, MP 0.00 to MP 8.52. **CONTAINS APPRENTICE UTILIZATION REQ: 15%.** Requires: Completing pavement repair, grind and inlay of HMA, crack sealing all ramps except at I-205, upgrading guardrail and signing, traffic control and other work. 40 Working Days. Involves 56 items. 1020 SY pvmt repair excav incl haul, 253760 SY plane bit pvmt, 26400 T HMA CL 1/2 IN PG 64-22, 171 EA inlet protect, 833 LF raise exist beam guardrail, 147060 LF paint line, 52300 LF plastic line, 101840 LF profiled plastic line, 20000 LF plastic wide line, 175880 LF temp pvmt marking, 946 SF const signs CL A. Lump Sum Bids for: Perm signing, ramp meter sys, temp traffic control, SPCC plan. (XL-3716)(401410A)(10X302)(7909)(5 of 4)(5)(2)

BID OPENING WEDNESDAY, APRIL 7, 2010

- *1. **(KING) SUNSET WAY CONNECTION INTERCHANGE MODIFICATIONS**
 (CL 1, \$1,500,000 - \$2,000,000) **CONTAINS CONDITION OF AWARD DBE GOAL: 18%.** F.A. No. IM-0901(461) on I-90, Vicinity MP 18.06. Requires: Roadway widening, slope construction, stormwater pond re-configuration, sidewalk, curb and gutter construction, installation of guardrail, paving, drainage, signal improvements, permanent signing, pavement marking, planting, erosion control, traffic control and other work. 75 Working days. Involves 129 items. 19800 T gravel borrow incl haul, 10700 CY embankment comp, 2551 CY pond excav incl haul, 112 T light loose rip rap, 282 LF underdrain pipe, 838 LF sch A storm sewer pipe, 725 LF ductile iron pipe, 1020 SY conc liner, 2923 SY plane bit pvmt, 1854 T HMA CL 1/2 IN PG 64-22, 2444 SY plastic covering, 1079 LF silt fence, 1630 LF compost sock, 597 CY topsoil, 918 EA salal, 536 EA pacific willow, 805 EA red-osier dogwood, 364 EA slough sledge, 842 LF cement conc traffic curb, 532 LF beam guardrail, 1455 LF temp conc barrier, 4056 LF paint line, 3095 LF plastic wide line, 4595 LF temp pvmt marking, 3502 SF shoring or extra excav CL B, 231 SY cement conc sidewalk, 515 SY reinforced edge cement conc sidewalk, 662 LF pedestrian hand rail, 568 LF coated chain link fence. **CONTAINS MINIMUM BID ITEM: TYPE B PROGRESS SCH.** Lump Sum bids for: Dewatering sys, temp conveyance sys, perm signing, traffic signal sys, temp video detect sys, temp traffic control, pedestrian control & protect, rdwy survey, health and safety plan, SPCC plan. (XL-3321)(109061D)(09A032)(7917) (3 of 4)

- *2. (SNOHOMISH) **SAFETY IMPROVEMENTS** (CL 1, \$4,000,000 - \$5,000,000) **CONTAINS VOLUNTARY MWBE GOAL: 17%. A State Project on US 2, MP 15.40 to MP 28.92. CONTAINS APPRENTICE UTILIZATION REQ: 15%.** Requires: Constructing a two way left turn lane, grading, roadway excavation, paving with hot mix asphalt, drainage, storm sewer, retaining wall, guardrail, bridge rail retrofit, concrete barrier, intelligent traffic system, illumination, sidewalks, pavement marking, erosion control, traffic control and other work. 80 Working days. Involves 140 items. 3320 CY rdwy excav incl haul, 3480 T gravel borrow incl haul, 2364 LF underdrain pipe, 1554 LF sch A storm sewer pipe, 330 LF bridge rail, 330 LF sew pedestrian barrier, 3610 SF struct earth wall, 3310 T crushed surface base course, 4750 T HMA CL 1/2 IN PG 58-22, 6950 SY temp erosion control blanket, 2990 SY stabilized const entrance, 1012 CY topsoil, 174 EA beaked hazelnut, 382 EA compact oregon grape, 1318 EA salal, 659 EA snowberry, 292 EA western serviceberry, 293 CY coarse compost, 3640 LF high visibility fence, 330 CY media filter drain mix, 153 SY dry native seed seeding & mulching, 1026 LF cement conc traffic curb & gutter, 3590 LF beam guardrail, 15 EA beam guardrail non-flared term, 470 LF single slope conc barrier, 3505 LF temp conc barrier, 15520 LF plastic line, 9700 LF grooved plastic line, 37800 LF temp pvmt marking, 4200 CY struct excav CL B incl haul, 12330 SF shoring or extra excav CL B, 690 SY cement conc sidewalk, 3530 SF gravity block wall, 2750 SY const geotextile. **CONTAINS MINIMUM BID ITEM: TYPE B PROGRESS SCH.** Lump Sum Bids for: Selective clear, grub & prune, perm signing, cantilever sign struct, illum sys, video, voice & data dist & trans sys, VMS, temp traffic control, pedestrian control & protect, detention vault, SPCC plan.(XL-3314)(100224I)(10A007)(7916)(3 of 4)
- *3. (SNOHOMISH) **164TH ST SW SOUTHBOUND OFF-RAMP CHANNELIZATION** (CL 9, \$250,000 - \$300,000) **CONTAINS CONDITION OF AWARD DBE GOAL: 12%. F.A. No. STPUL-0054(279) on I-5, MP 183.90 to MP 184.19.** Requires: Re-channeling off- ramp, modifying existing traffic island, replacing signal pole and mast arm, removing earth berm and concrete barrier, installing guardrail, replacing or modifying existing curb ramps, replacing deficient signs, pavement marking, erosion/water pollution control, traffic control and other work. 20 Working days. Involves 41 items. 57 CY rdwy excav incl haul, 46 T HMA CL 1/2 IN PG 64-22, 92 LF cement conc ped curb, 111 LF precast sloped mountable curb, 1361 LF plastic line, 994 LF plastic wide lane line, 50 SF ramp detectable warning retrofit. Lump Sum Bids for: Perm signing, temp traffic signal sys, traffic signal & illum sys, temp traffic control, pedestrian control and protect, rdwy survey SPCC plan.(XL-3605)(100540D)(10A003)(7919)(2 of 3)
- *4. (KING) **MT BAKER TUNNEL & MERCER ISLAND LID PLC REPLACEMENT** (CL 41, \$750,000 – \$1,000,000) F.A. No. IM-0901(450) on I-90, MP 3.57 to MP 6.56. Requires: Designing, furnishing, installing, testing, providing operation and maintenance training, and placing into operation the new Programmable Logic Controllers system that will replace the existing SY/MAX PLC system. 200 Working days. Involves 4 items. Lump Sum Bid for: Lid PLC replacement.(XL-2808)(109067S)(09A031)(7908) (5 of 4)6(2)
- *5. **“THIS PROJECT IS FUNDED IN WHOLE OR IN PART BY FUNDS MADE AVAILABLE THROUGH THE AMERICAN RECOVERY AND REINVESTMENT ACT”**
 ** (COWLITZ) **1 MILE E OF ROCK CREEK BR. TO FREDRICKSON RD. – PAVING** (CL 4, \$2,000,000 - \$2,500,000) **CONTAINS CONDITION OF AWARD DBE GOAL: 10%. F.A. No. ARRA-STPF-0503(023) on SR 503, MP 35.50 TO MP 45.97. CONTAINS APPRENTICE UTILIZATION REQ: 15%.** Requires: Planing bituminous pavement, paving with hot mix asphalt, addressing guardrail deficiencies, installing pavement marking & erosion control BMP's, traffic control and other work. 40 Working days. Involves 60 items. 127450 SY plane bit pvmt, 14426 T HMA CL 1/2 IN PG 64-22, 510 LF silt fence, 510 LF wattle, 1129 EA beam guardrail post, 787 LF beam guardrail, 5789 LF raise exist beam guardrail, 130 LF precast conc barrier, 16850 LF paint line, 13 HUND recessed pvmt marker, 55281 LF temp pvmt marking. Lump Sum Bids for: Perm signing, temp traffic control, SPCC plan. (XL-3598) (450309P)(10X303)(7910)(5 of 4)6(3)

BID OPENING WEDNESDAY, APRIL 14, 2010

- *1. (KING) **ALASKAN WAY VIADUCT – REPLACEMENT – S HOLGATE ST TO KING ST – STAGE 2** (CL 1 or 6, \$125,000,000 - \$175,000,000) **CONTAINS CONDITION OF AWARD DBE GOAL: 10%.**
** F.A. No. PNRs-0099(096 & 097) on SR 99, MP 28.85 to MP 31.75. **CONTAINS APPRENTICE**
*** **UTILIZATION REQUIREMENT: 15%.** Requires: Constructing bridges, utility relocation work, paving with HMA and cement concrete, constructing walls, demolishing the existing SR 99 elevated roadway, grading for railroad tracks, excavating and disposing of contaminated materials, pile work, pedestrian/bicycle shared use path, cement deep soil mixing, traffic control, traffic signal system and illumination work, pavement marking, guardrail, fencing, temporary water pollution and erosion control, traffic control and other work. 1560 Working days. Involves 195 items. 75319 CY rdwy excav incl haul, 54319 T gravel borrow incl haul, 3934 CY unstable base material backfill, 24441 CY geofabric lightweight fill, 190203 T dispose contaminated material, 7 EA in-line water quality vault, 7643 LF SD CL V reinf conc storm sewer pipe, 399 LF st casing, 8889 LF storm sewer pipe, 109 EA manhole, 207 EA catch basin, 121110 CY struct excav CL A incl haul, 49033 CY soil excav incl haul 68010 LF furnish & place temp casing, 908 LF furnish perm casing, 78 EA place perm casing, 230 LF casing shoring, 10728 LF furnish conc piling, 56 EA drive conc pile, 2359 LF furnish st piling, 2121850 LB epoxy-coated st rebar, 11634831 LB st rebar, 175280 LF CSL access tube, 2831 CY lean conc, 9302 CY conc CL 4000D, 8760 CY conc CL 4000, 19175 CY conc CL 4000P, 65845 LF prestressed conc girder, 15572 SY waterproofing, 1015 SY bridge approach slab, 58 EA furnish st pile tip or shoe, 24090 T crushed surface base course, 4280 T railroad sub-ballast, 4962 CY cement conc pvmt, 10762 EA corrosion resistant dowel bar, 6836 CY COS cement conc pvmt incl dowels, 16898 T HMA CL 1/2 IN PG 64-22, 1168 T commercial HMA, 3 EA tire wash, 15117 LF temp conc barrier, 48 EA sch update, 1470 LF temp chain link security fence, 21610 SF shotcrete facing, 33 EA pumping well, 15 EA recharge well, 5300 CY pretrenching, 40200 CY CDSM panel, 5200 CY jet grout. **CONTAINS MINIMUM BID ITEMS: TYPE C PROGRESS SCH. HOURLY WAGE FOR OTHER TRAFFIC CONTROL LABOR AND FLAGGERS/SPOTTERS.** Lump Sum Bids for: Geotech instrumentation, water quality vault, pre-treatment vault, storm sewer plug, remove, abandon, flow splitter vault, grit storage chamber vault, shutoff valve manhole, PSD pump station, combined sewer sys in place, water sys in place, shoring or extra excav CL A, struct carbon st, struct low alloy st, column jacket, rdwy deck, retained fill approach walls, temp column support, overhead coiling door, metal grating, erosion control elements, port stormwater treatment facility, port process water treatment facility, temp drain, temp pvmt marking, perm signing, sign bridges, illum sys, temp illum sys, traffic signal sys, flashing beacon sys, CCTV, communication conduit sys, communication cable and interfaces, video, voice & data dist & trans sys, VMS, perm pvmt marking, temp traffic control, shoring, cure box, struct survey, rdwy & utility survey, fences & gates, clean exist drain struct, utility coordinator, adjust utility objects, OCR and kiosk sys, urban design elements, terminal 46 electrical, dewatering sys design, utility crossing cathodic protect, dewatering sys, 26KV underground sys in place, 26 KV overhead sys in place, fire protect sys, field office, poly conc trial overlay, SPCC plan. **SUPERSTRUCTURE INCLUDES:** 1597707 LB epoxy-coated st rebar, 330045 LB st rebar, 8088 CY conc CL 4000D, 1262 CY conc CL 4000, 432 LF expansion jnt sys strip seal, 291 EA elastomeric bearing pad, 286 EA elastomeric girder stop pad, 23212 LF conduit pipe, 15 EA bridge drain, pipes & support brackets, 8931 LF traffic barrier, 1224 LF median barrier, 84 LF median barrier trans, 15 EA longitudinal seismic restrainer, 950 LF safety net, 2 sets bridge drain grates, 90 LF expansion jnt sys, 262 LF bridge deck drain sys, 4 EA transverse stop bearing, 100 LF prestressed conc girder PCPS slab, 10230 LB struct low alloy st, 13 LF expansion jnt sys silicone seal, 621 LF expansion jnt sys compression seal, 130 LF throw fence, 516 EA drill holes, 3 EA mod bridge drains, 4 EA plug exist drain.(XL-3237) (809936D)(09A803)(7847)(22 of 40)24)(8) **GEOTECH REPORT AVAILABLE AT:**
www.wsdot.wa.gov/biz/contaa
- *2. (KING) **160TH AVE SE TO COVINGTON CITY LIMITS – PAVING** (CL 4, \$1,250,000 - \$1,500,000) **CONTAINS CONDITION OF AWARD DBE GOAL: 13%.** F.A. No. STPF-0516(021) on SR 516, MP 11.09 to MP 12.31. Requires: Planing and paving, pavement repair, crack sealing, permanent signing, pavement markings, curb ramps and modifications, traffic signal loops, erosion/water pollution control, traffic control and other work. 65 Working days. Involves 63 items. 311 CY rdwy excav incl haul, 212 T crushed surface base course, 43210 SY plane bit pvmt, 4841 T HMA CL 1/2 IN PG 64-22, 4393 LF plastic wide line, 9361 SF plastic crosswalk line, 41885 LF temp pvmt marking, 97 EA loop replace, 1000 HR contractor provided uniformed officer, 27 EA mod cement conc curb ramp. **CONTAINS MINIMUM BID ITEM: TYPE B PROGRESS SCH.** Lump Sum Bids for: Perm signing, temp video detection sys, electrical sys mod, temp traffic control, pedestrian control and protect, reference exist pvmt marking, rdwy survey, SPCC plan.(XL-3013)(151626P)(10A009)(7921)(2 of 4)

3. (COWLITZ & LEWIS) **SW REGION PAVEMENT MARKINGS** (CL 12, \$200,000 - \$250,000) F.A. No. IM-0051(282) on I-5, MP 50.12 to MP 64.85. Requires: Removing raised pavement markers, installing profiled plastic lane line & raised pavement markers, traffic control and other work. 20 Working days. Involves 9 items. 215880 LF profiled plastic line. Lump Sum Bids for: Temp traffic control, SPCC plan.(XL-3608)(400509P)(10X307)(7927)(1 of 3)
4. (SAN JUAN) **SHAW ISLAND FERRY TERMINAL DOLPHIN REPLACEMENT** (CL 6, \$2,000,000 - \$2,500,000) A State Project for Washington State Ferries. **CONTAINS APPRENTICE UTILIZATION REQUIREMENT: 15%**. Requires: Replacing two existing timber pile dolphins with two new steel dolphins and other work. 160 Working days. Involves 26 items. 70 CY conc CL 4000, 30 EA furnish st pile tip or shoe, 2313 LF furnish st piling, 840 LF fabricate st piling, 30 EA drive st pile, 7 EA furnish rock socket materials, 5 EA install rock socket, 9 EA marine fender, 9 EA UHMW polyethylene rubbing face. Lump Sum Bids for: Epoxy-coated st rebar, struct low alloy st, chain & hardware, temp protective dolphin, marine survey, bird deterrent sys, SPCC plan.(XL-3476)(900024F)(09W171)(7922)(1 of 3)

BID OPENING WEDNESDAY, APRIL 21, 2010

1. (KING) **BR 90/50N & SR 520/I-405 VICINITY SEISMIC RETROFIT** (CL 6, \$4,000,000 - \$5,000,000) **CONTAINS VOLUNTARY MWBE GOAL: 5%**. A State Project on SR 520, MP 6.90 to MP 8.83 and I-90 at MP 9.88. **CONTAINS APPRENTICE UTILIZATION REQ: 15%**. Requires: Steel column jacket installation, girder stop, cross-beam bolster and infill wall construction, girder splicing, erosion control, traffic control and other work. 310 Working days. Involves 68 items. 980 SY stabilized const entrance, 1625 LF temp conc barrier, 1700 LF plastic line. **CONTAINS MINIMUM BID ITEM: TYPE B PROGRESS SCH.** Lump Sum Bids for: Shoring or extra excav CL A, seismic retrofit, column jacketing, illum sys, temp traffic control, pedestrian control and protect, health & safety plan, SPCC plan. **SEISMIC RETROFIT INCLUDES:** 123344 LBS st rebar, 684 CY conc CL 4000, 92 EA transverse girder stop pads, 4514 LF drill holes, 16 EA contracting agency provided elastomeric bearing pads, 1600 SF perm st sheet pile shoring, 1281 CY struct excav CL A incl haul, 1120 CY controlled density fill, 4386 SF expanded polystyrene, 56 CY selective demolition, 1 EA struct lift sys, 76 LF remove & replace precast traffic barrier, 55 LF perm traffic barrier removal, 80 LF remove & replace cement conc traffic curb & gutter, 140 SY remove & replace cement conc sidewalk, 180 SY remove conc slope protect, 80 LF remove & replace catch basin, 40 LF remove and replace chain link fence. **COLUMN JACKETING INCLUDES:** 416 LF remove & replace underdrain, 917 CY struct excav CL A incl haul, 491 CY backfill, 1580 SF rock wall remove & replace, 163989 LBS struct st, 74 CY grout, 250 LF remove & replace cement conc sidewalk, 120 LF remove & replace cement conc traffic curb & gutter, 280 LF remove, store, replace metal railing, 448 LF remove & reset precast traffic barrier, 120 SY remove & replace cement conc sidewalk, 200 LF remove & reset beam guardrail, 150 SY remove & replace conc slope protect, 9 CY select demolition, 20 SY remove & replace slope protect, 280 SF remove & replace exist portion of existing conc, 300 LF remove & reset cable hand rail, 240 LF remove & replace chain link fence.(XL-3366)(109051S)(10A004)(7925)(1 of 4)

BID OPENING WEDNESDAY, APRIL 28, 2010

- *1. (SNOHOMISH) **LUNDEEN PARKWAY TO SR 92 INTERSECTION IMPROVEMENTS AND WIDENING** (CL 1 or 6, Under \$20,000,000) **CONTAINS VOLUNTARY MWBE GOAL: 13%**. A State Project on SR 9, MP 16.12 to MP 17.67. **CONTAINS APPRENTICE UTILIZATION REQ: 15%**. Requires: Grading, surfacing, paving with hot mix asphalt, structure excavation, shoring, embankment compaction, soldier pile walls, detention pond structure, drainage systems, pavement marking, landscaping, illumination, traffic signal systems, intelligent transportation system, permanent signing, guardrail, concrete traffic barrier, erosion control, traffic control and other work. 180 Working days. Involves 221 items. 79010 CY rdwy excav incl haul, 7280 CY unsuitable foundation excav incl haul, 55560 T gravel borrow incl haul, 18150 CY embank comp, 11900 CY pond embank comp, 1704 CY ditch excav incl haul, 391 T quarry spalls, 369 LF CL V reinf conc culv pipe, 388 LF temp culv pipe, 63 EA catch basin, 6180 LF test storm sewer pipe, 5737 LF sch A storm sewer pipe, 1520 CY struct excav CL A incl haul, 1124 CY gravel backfill, 5141 LF shaft, 7880 LF furnish soldier pile, 19032 LB st rebar, 253 CY conc CL 4000, 21113 SF precast conc panels, 147 EA perm ground anchor, 17050 T crushed surface base course, 19367 T HMA CL 1/2 IN PG 64-22, 8030 LF silt fence, 20409 LF compost sock, 1220 LF temp curb, 7 ACRE mulch, 507 CY topsoil, 4387 EA baldhip rose, 1889 EA beaked hazelnut, 2002 EA douglas fir, 2182 EA elderberry, 26434 EA salal, 5103 EA scoulers willow, 5110 EA snowberry, 2025 EA western red cedar, 3410 CY coarse compost, 3018 CY bark or wood chip mulch, 7730 LF high visibility fence, 4572 LF extruded curb, 2761 LF beam guardrail, 3305 LF precast conc barrier, 10425 LF temp conc barrier, 23935 LF paint line, 18130 LF profiled

plastic line, 14 HUND raised pvmt marker, 144920 LF temp pvmt marking, 690 LF directional boring, 796 SF const signs CL A, 8735 CY struct excav CL B incl haul, 35803 SF shoring or extra excav CL B, 2400 T pipe zone backfill, 19 EA cement conc sidewalk ramp, 2762 LF chain link fence, 7770 LF wire fence, 10920 SY const geotextile. **CONTAINS MINIMUM BID ITEM: TYPE B PROGRESS SCH.** Lump Sum Bids for: Temp stream bypass, dispersion trenches, trench drain, shoring or extra excav CL A, perm ground anchor verification test, detention pond vault, stormwater vault mod, perm signing, illum sys, traffic data accumulation and ramp meter sys, temp traffic signal sys, traffic signal sys, CCTV, communication conduit sys, communication cables & interfaces, video, voice & data dist & trans sys, temp traffic control, cure box, struct survey, field office bldg, abandonment of piezometer, SPCC plan. (XL-3041)(100917G) (09A009)(7920)(2 of 6)

BID OPENING WEDNESDAY, MAY 5, 2010

1. (KITSAP) **MANETTE BRIDGE 303/4A – BRIDGE REPLACEMENT** (CL 6, \$30,000,000 - \$45,000,000) **CONTAINS CONDITION OF AWARD DBE GOAL: 7%. F.A. No. BR-0303(005)** in the City of Bremerton. **CONTAINS APPRENTICE UTILIZATION REQ: 15%**. Requires: Removing an existing steel girder and steel truss bridge, construction a prestressed, post-tensioned concrete girder bridge, shafts, piers, abutments and superstructure, reconstructing an intersection and constructing a roundabout, in-water bridge construction & demolition, wall construction, grading, drainage, surfacing, paving with hot mix asphalt, illumination systems, pavement markings, roadside seeding and planting, permanent signing, traffic control and other work. 357 Working days. Involves 211 items. 1050 CY rdwy excav incl haul, 5960 T gravel borrow incl haul, 30 EA streambed boulder, 16 EA catch basin, 835 LF solid wall pvc storm sewer pipe, 1148 LF ductile iron sewer pipe, 175 LF PVC sanitary sewer pipe, 2117 LF ductile iron pipe, 4780 CY soil excav incl haul, 547 LF furnish perm casing, 12 EA place perm casing, 113 LF casing shoring, 2310600 LB epoxy-coated st rebar, 1889000 LB st rebar, 16700 LF CSL access tube, 5340 CY conc CL 4000, 5820 CY conc CL 4000P, 6070 LF prestressed conc girder, 32 EA high-load elastomeric bearing pad, 3200 LF bridge rail, 227 LF st walkway rail, 1600 LF traffic barrier, 1600 LF pedestrian barrier, 2241 SF struct earth wall, 290 SY bridge approach slab, 967 T HMA CL 1/2 IN PG 64-22, 622 SY stabilized const entrance, 1330 LF silt fence, 100 EA hebe, 22 EA flame grass, 300 EA Indian plum, 300 EA nootka rose, 150 EA evergreen huckleberry, 290 CY fine compost, 290 CY bark or wood chip mulch, 400 SY sod install, 623 LF cement conc traffic curb & gutter, 4020 LF paint line, 8 HUND raised pvmt marker, 69 LF furnish perm casing, 11 EA install perm casing, 8924 LF conduit pipe, 1011 SF const signs CL A , 2519 CY struct excav CL B incl haul, 8760 SF shoring or extra excav CL B, 631 SY cement conc sidewalk, 472 SY viewscape cement conc sidewalk, 96 SY patterned & pigmented conc, 4600 HR training. **CONTAINS MINIMUM BID ITEM: TYPE B PROGRESS SCH.** Lump Sum Bids for: Infiltration gallery, shoring or extra excav CL A, barrier XBM wall & girder closure form test section, mod expansion jnt sys, irrigation sys, seeding, perm signing, illum sys, traffic signal sys, temp traffic control, pedestrian control & protect, cure box, struct survey, navigation lighting sys, clean exist drain struct, field office bldg, health & safety plan, SPCC plan. **SUPERSTRUCTURE INCLUDES:** 711500 LB epoxy-coated st rebar, 38300 LB st rebar, 1990 CY conc CL 4000D, 1120 CY conc CL 4000, 293000 LB prestressed conc girder post-tensioning reinforcement, 52 EA transverse elastomeric girder stop pad, 1 EA valve box casting, 6 EA bridge deck drain assembly, 2520 LB insert for bridge deck drainage sys & bridge utility support.(0L-2829)(330311A)(09C526)(7926)(1 of 6)

Paula J. Hammond, P.E.
Secretary of Transportation

* Previously Advertised
** Extended
*** Revised

Projects awarded the week of March 15, 2010

(Clark) Lewisville Park Vic. Climbing Lanes - #7882 – Rotschy, Inc., Yacolt, WA 98675 - \$3,701,706.53

(King) Roadside Safety Improvements - #7902 – Coral Construction Company, Sherwood, OR 97140-9563 - \$637,777.00

(Snohomish) Skaglund Hill Slide Wetland Mitigation - #7894 – Trimaxx Construction, Inc., Sedro Woolley, WA 98284-7516 - \$593,288.40